


OECD approval number OECD approval date Make Model Type Manufacturer: Testing station:

2/2 688 22/03/2012 CASE IH Magnum 340 4WD Power Shift - 40 km/h CNH America LLC Nebraska Tractor Test Laboratory Lincoln, Nebraska U.S.A.



ORGANISATION FOR ECONOMIC CO-OPERATION AND DEVELOPMENT





Engine, Transmission, Power take-off Specifications Make, Model Type, Supercharging Cylinders, Disposition Capacity, Cooling Gear box Number of forward and reverse speeds Speed at rated engine speed	FPT Direct injection 6 8704 cm ³	19 from 3,15	Cursor 9L Yes vertical in line Liquid Power Shift 4 to 45,75 km/h
<u>Standard Power take-off speed</u> Power take-off speed at rated engine speed Diameter of the shaft Number of splines		540 min ⁻¹ 597 min ⁻¹ 35 mm 6	1000 min ⁻¹ 1109 min ⁻¹ 44 mm 20
Power take-off Test			
<u>One hour test at maximum power</u> <i>Power, Engine and Power take-off speed</i> <i>Hourly and specific consumption</i> <u>Test at maximum power at rated engine speed</u>	251,58 kW	1650 min ⁻¹ 63,42 l/h	915 min ⁻¹ 213 g/kWh
Power, Engine and Power take-off speed Hourly and specific consumption Test at standard Power take-off speed	220,00 kW	2000 min ⁻¹ 58,05 l/h	1110 min ⁻¹ 223 g/kWh
Power, Engine and Power take-off speed Hourly and specific consumption Torque rise	247,16 kW	1804 min ⁻¹ 62,76 l/h	1000 min ⁻¹ 214 g/kWh 45,7 %
Maximum torque, Engine speed corresponding		1530 Nm	1500 min ⁻¹
Drawbar Test		420/90R30	520/85R42
Front tyres, Rear tyres Test with tractor		unballasted	ballasted
Total Mass		12025 kg	16776 kg
Maximum drawbar pull		116,71 kŇ	165,99 kN
at speed of		5,07 km/h	3,75 km/h
Maximum power		218,69 kW	218,08 kW
at speed of		8,77 km/h	7,69 km/h
Hydraulic Performance and Power Lift Test			
Hydraulic system At maximum hydraulic power			Closed centre
Flow rate, Pressure, Power (couplers: 1 pair)	146,6 l/min	14,96 MPa	36,6 kW
Flow rate, Pressure, Power (couplers: 2 pairs or +)	226,0 l/min	17,71 MPa	66,7 kW
Maximum lifting force		77 0 1 11	(0.4.13)
at the hitch points, at frame		77,9 kN	63,4 kN



