


OECD approval number OECD approval date Make Model Type

Manufacturer: Testing station: 2/2 783
19/09/2013
Challenger
MT755D
Rubber Tracklaying
Full PowerShift - 40 km/h
AGCO Corporation
Nebraska Tractor Test Laboratory
Lincoln, Nebraska U.S.A.







| Engine, Transmission, Power take-off Specifications | | | |
|---|---------------------|------------------------|------------------------|
| Make, Model | AGCO Power | | 84AWI777 |
| Type, Supercharging | Direct injection | | Yes |
| Cylinders, Disposition | 6 | | vertical in line |
| Capacity, Cooling | 8419 cm^3 | | Liquid |
| Gear box | | | Full PowerShift |
| Number of forward and reverse speeds | | 16 | 4 |
| Speed at rated engine speed | | from 2,67 | to 39,65 km/h |
| Standard Power take-off speed | | 540 min ⁻¹ | 1000 min ⁻¹ |
| Power take-off speed at rated engine speed | | | 1061 min ⁻¹ |
| Diameter of the shaft | | Not | 44,45 mm |
| Number of splines | | Applicable | 20 |
| | | | |
| Power take-off Test | | | |
| One hour test at maximum power | | | |
| Power, Engine and Power take-off speed | 236,77 kW | 1800 min ⁻¹ | 909 min ⁻¹ |
| Hourly and specific consumption | | 61,94 l/h | 220 g/kWh |
| Test at maximum power at rated engine speed | | | |
| Power, Engine and Power take-off speed | 209,85 kW | 2101 min ⁻¹ | 1061 min ⁻¹ |
| Hourly and specific consumption | | 58,58 l/h | 234 g/kWh |
| Test at standard Power take-off speed | | | |
| Power, Engine and Power take-off speed | 230,09 kW | 1980 min ⁻¹ | 999 min ⁻¹ |
| Hourly and specific consumption | | 62,47 l/h | 228 g/kWh |
| Torque rise | | | 47,7 % |
| Maximum torque, Engine speed corresponding | | 1408,6 Nm | 1501 min ⁻¹ |
| | | | |
| Drawbar Test | | | |
| Front tyres, Rear tyres | | - | - |
| <u>Test with tractor</u> | | unballasted | <u>ballasted</u> |
| Total Mass | | 14222 kg | 16254 kg |
| Maximum drawbar pull | | 137,93 kN | 159,04 kN |
| at speed of | | 3,76 km/h | 3,43 km/h |
| Maximum power | | 211,36 kW | 212,76 kW |
| at speed of | | 9,80 km/h | 9,88 km/h |
| • | | | |
| Hydraulic Performance and Power Lift Test | | | |
| Hydraulic system | | | Closed centre |
| At maximum hydraulic power | | | |
| Flow rate, Pressure, Power (couplers: 1 pair) | 149,8 1/min | 15,95 MPa | 39,8 kW |
| Flow rate, Pressure, Power (couplers: 2 pairs or +) | 161,7 l/min | 19,76 MPa | 53,3 kW |
| Maximum lifting force | , | , | , |
| at the hitch points, at frame | | 81,7 kN | 76,8 kN |
| | | , | ,- 111 |



