



OECD approval number  
 OECD approval date  
 Make  
 Model  
 Type


2/2 825  
 07/04/2014  
 Massey Ferguson  
 5612  
 4WD

Mechanical synchromesh - 40 km/h  
 AGCO S.A  
 IRSTEA - France

Manufacturer:  
 Testing station:

Massey Ferguson 5612  
 4WD

OCDE/OECD 2/2 825



## Engine, Transmission, Power take-off Specifications

<i>Make, Model</i>	AGCO POWER	44 AWIC 905
<i>Type, Supercharging</i>	Direct injection	Yes
<i>Cylinders, Disposition</i>	4	vertical in line
<i>Capacity, Cooling</i>	4397 cm <sup>3</sup>	Liquid
<i>Gear box</i>		Mechanical synchromesh
<i>Number of forward and reverse speeds</i>		16 16
<i>Speed at rated engine speed</i>		from 2,13 to 43,62 km/h
<u>Standard Power take-off speed</u>		540 min <sup>-1</sup> 1000 min <sup>-1</sup>
<i>Power take-off speed at rated engine speed</i>		618 min <sup>-1</sup> 1122 min <sup>-1</sup>
<i>Diameter of the shaft</i>		34,9 mm 34,9 mm
<i>Number of splines</i>		6 21

## Power take-off Test

### One hour test at maximum power

<i>Power, Engine and Power take-off speed</i>	77,3 kW	1999 min <sup>-1</sup>	1017 min <sup>-1</sup>
<i>Hourly and specific consumption</i>		23,19 l/h	252 g/kWh

### Test at maximum power at rated engine speed

<i>Power, Engine and Power take-off speed</i>	71,3 kW	2198 min <sup>-1</sup>	1118 min <sup>-1</sup>
<i>Hourly and specific consumption</i>		23,01 l/h	270 g/kWh

### Test at standard Power take-off speed

<i>Power, Engine and Power take-off speed</i>	76,9 kW	1966 min <sup>-1</sup>	1000 min <sup>-1</sup>
<i>Hourly and specific consumption</i>		23,04 l/h	251 g/kWh

### Torque rise

<u>Maximum torque, Engine speed corresponding</u>		456,1 Nm	1500 min <sup>-1</sup>
---	--	----------	------------------------

## Drawbar Test

<i>Front tyres, Rear tyres</i>	380/70 R28	520/70 R38
<u>Test with tractor</u>	<u>unballasted</u>	<u>ballasted</u>
<i>Total Mass</i>	5020 kg	
<i>Maximum drawbar pull</i>	45,6 kN	
<i>at speed of</i>	3,52 km/h	Not
<i>Maximum power</i>	65,6 kW	Applicable
<i>at speed of</i>	9,21 km/h	

## Hydraulic Performance and Power Lift Test

<i>Hydraulic system</i>			Open centre
<u>At maximum hydraulic power</u>			
<i>Flow rate, Pressure, Power (couplers: 1 pair)</i>	94,8 l/min	13,1 MPa	20,8 kW
<i>Flow rate, Pressure, Power (couplers: 2 pairs or +)</i>	100,5 l/min	14,8 MPa	24,8 kW
<u>Maximum lifting force</u>			
<i>at the hitch points, at frame</i>		45,6 kN	42,0 kN